

1909101 Quad Upgrade ESS - Pre Bid RFI Tracker - 9/10/2024

1- 64

RFI #	RFI Question	RFI Answer	Date Answered	Image / Sketch / Reference Etc.	Requires Drawing / Spec update
1	EPP1 has 11 symbols in the middle of the rooms which are a square with FB in it. This symbol does not appear in the symbol list, but it is assumed this is a floor box. Please confirm the floor type in this area, and how access is to be obtained to install the floor boxes.	These 11 floorboxes are for power; 3120 & 3036. Floor types are RT1 finish per A-701SHP1	8/26/2024	E-401 EPP1	
2	Is the contractor expected to provide a temporary guard booth as the new one is getting installed?	Yes, GC to provide a temporary guard booth.	9/5/2024		
3	Please confirm that there is an existing telecom service drop/infrastructure, and no new conduit is expected to be run from the guard to a command center.	No conduit is required to be ran from the Guard Booth to the Command Center	8/6/2024		
4	Is the contractor responsible for relocating the furniture or existing office equipment?	GC is responsible for temporarily relocating furniture to perform work.	9/5/2024		
5	The classrooms are in use well before the museum opens, what are the expected working hours?	Working hours are listed in Div 010000 Part 3.1. Contractor's construction schedule should consider phasing to minimize impact to classrooms.	8/26/2024		
6	What is the project's anticipated award time frame?	Before September 30, 2024. End of 1st quarter FY 25	9/9/2024		
7	What is the existing fire alarm system?	Siemens XLS	8/6/2024		
8	Please provide contact information for the company that maintains the fire alarm system.	James Gates Operational Manager 240280 6983	8/26/2024		
9	What is the existing proprietary electronic access control system (ePACs)?	Software House	8/6/2024		
10	Please provide contact information for the company that maintains the existing electronic access control system.	Parson: Scott Butler Operational Manager 202 658 4914 Get Wired: Christine Operational Manager 301 524 9955	8/26/2024		
11	Please confirm that existing electrical and water utilities are available for the Contractor's use and free of charge.	Confirmed	8/6/2024	Temporary Utility Services and Extensions	
12	Please confirm if the Superintendent can also be a Quality Manager & Site Safety Officer on this project.	Yes, if they meet the specification requirements.	8/6/2024	Supervision	
13	Please confirm that no other personnel required aside from Superintendent/QCM/SSHO.	Refer to specifications.	8/6/2024	Supervision Team	
14	Are we required to have a separate team for normal and off-hours work. If yes, please confirm if an alternate superintendent is enough to fill the supervision requirement during off-hours work.	Refer to specifications and your means and methods.	8/6/2024	Supervision Team	
15	Please clarify if hiring Commissioning Agent (CxA) is the responsibility of General Contractor.	GC must provide a third party inspector, but not a commissioning agent.	8/26/2024	Commissioning	
16	Please provide sign-in sheet	Provided as attachment.	8/6/2024	Sign-In Sheet	
17	Please confirm that any supply or installation of FFE is the responsibility of the Government. If not, please provide a complete specification.	GC to supply and install FFE for OPS Suite, OPS Command Center, and one chair for guard booth. Refer to Product Data. Furniture and AV equipment in classrooms are excluded from scope.	9/9/2024	FFE	
18	Please provide site utility as-built drawings where the new guard booth is located.	Site Utilities Plan for Quadrangle Building is attached.	8/26/2024	Site Utility As-Built	

1909101 Quad Upgrade ESS - Pre Bid RFI Tracker - 9/10/2024

19	A-008P1 is calling out for a curb along the perimeter of guard booth. However, Sections in A-012P1 show slab on grade with same elevation to the ground. Please clarify which is correct and provide details of the curb if needed.	Flush slab edge intended to extend 6 inches beyond outer face of guardbooth wall to serve as protective edge from mowers.	8/26/2024	A-008P1 & A-012P1	
20	Is the highlighted portion of the drawing a concrete curb? Please clarify and provide details.	Highlighted portion is not a curb.	8/26/2024	A-008P1	
21	Is the highlighted portion of the drawing a handicap ramp? Please clarify and provide details.	Design intent on the highlighted portion is NOT for accessible entry, accessible ramp is not required. GC is responsible for ensuring positive drainage away from the new guard booth and throughout the limits of disturbance.	9/5/2024	A-008P1	
22	Please provide specifications for stone cladding on guard booth	Refer to Spec 0444200.	8/26/2024	A-008P1	
23	Please provide sections of the clouded area of the drawing.	Sections will not provide significant information. The distance between the pull boxes and the booth is 2 feet. The exact conduit routings should be coordinated in the field.	9/5/2024	C-442EPP1	
24	Please provide duct bank details	There are no duct banks. These are direct buried conduits as shown.	9/5/2024	C-442EPP1	
25	Drawing E402EPP1 Sub Level 3 Room 3221 has 2 new circuits. One to PESEC and one to PSEC. These panels are located on sublevel 1. Please provide a pathway to run these conduits.	GC to determine best route in field for all conduits.	8/26/2024	E402EPP1	
26	Drawing E101FPP1 and Drawing E408EPP1. There are 2 new lighting circuits in the classroom. 1 from EHP3A and 1 from HP3A1. Please provide a pathway from the panels to the classroom locations. The area in between seems inaccessible.	GC to determine best route in field for all conduits.	8/26/2024	E101FPP1 and E408EPP1	
27	Drawing E601DGP1. Please provide a path for the new feeder from SWBD A to ECB TSEC.	GC to determine best route in field for all conduits.	8/26/2024	E601DGP1	
28	What level of Security Clearance is required by Smithsonian?	Special Agreement Checks (SACs)	8/26/2024		
29	Who is responsible for video wall equipment and installation?	Refer to Division 27 274116 specification	8/6/2024		
30	Who is responsible for Security Desk and Desk Monitors?	Refer to Division 28 281515 specification.	8/6/2024		
31	Who is responsible for wall penetration and cable pathways?	Electrical	8/6/2024		
32	Does a project schedule exist for the project? If so, can it be shared? If no schedule exists, can high-level milestone dates be provided? (i.e. construction start, construction completion)?	Project schedule is to be developed by the GC after contract award. Performance period is stated in specifications. High-level milestones will be discussed in the Pre-Con.	8/6/2024		
33	Can a site walkthrough be coordinated?	Site Walk occurred on July 17, 2024. No further site walks planned.	8/6/2024		
34	Please confirm a low voltage permit will be required.	Confirmed	8/6/2024		

1909101 Quad Upgrade ESS - Pre Bid RFI Tracker - 9/10/2024

35	Are there any areas in scope of work that contain asbestos?	The only known asbestos in the Quad is brown duct mastic and floor tile in Hallway 2014. If floor tile is to be disturbed in the scope, a visual inspection or testing is recommended to confirm if its is the ACM previously identified in Hallway 2014. An ACM report is attached.	9/5/2024		
36	Sheet TN201ELP1 Indicates network equipment provided and installed by owner. Please confirm owner is to provide and install all network equipment associated with this scope of work	Confirmed	8/6/2024	TN201ELP1	
37	Who is responsible for door and door frame prep for security equipment? (Holes drilled for contact, door cored for mortise locks, transfer hinge, etc.)	GC is responsible for work and will determine which trade is appropriate. Follow door schedule and security drawings.	8/26/2024		
38	Is security cabling to be done by Div. 28(Security Contractor) or Div 27?	The cabling requirements for security cables are found in Div 28. The cabling to the devices shall be done by DIV 28.	8/6/2024		
39	Who is responsible for door locking hardware? DIV.8 or DIV.28?	Division 28	8/6/2024		
40	Confirm what DIV is providing the UPS equipment?	Division 28 will provide UPS for the Security Servers	8/6/2024		
41	Confirm DIV.7 will be doing all Firestopping?	GC to determine which trade is appropriate	8/26/2024		
42	C*Cure 800/8000 End of life by Software House there is no support for this product. Confirm this this system be upgraded to C*Cure 900/9000 software?	Yes, upgrade to C*Cure 900/9000	8/6/2024		
43	Confirm that electrician will providing power for the UPS?	Confirmed	8/6/2024		
44	Please confirm that the government will handle removal, disposal or salvage of any equipment in Photo Lab.	Any remaining furniture or equipment by the start of construction will be the responsibility of the GC to remove. For bidding purposes, the salvage of the stainless steel sinks and lockers by SI can be assumed. All other equipment to be disposed of by GC.	8/26/2024		
45	Please provide the location/s where we need Level 3 Ballistic Rated Ceiling	3112E Weapons Room.	8/26/2024	F8/A-001P1 Design Drawing Page 8	
46	If room signage is required, please provide a room identification plan showing rooms and required type of signage.	Per spec 101423.16, new room-identification signs to match room name and number identified in areas of new work in the drawing set.	9/5/2024	Section 101423.16 Room-Identification Panel Signage	
47	If room signage is required, please provide signage detail layout	No signage detail at this time. Signage plans to be reviewed by SI and discussed at Pre-Con meeting.	9/5/2024	Section 101423.16 Room-Identification	
48	Please confirm that no work related to historic treatment of steel windows in this project. If there are, please provide locations which needs this Specification Section.	Confirmed, no window scope.	8/26/2024	Section 080351.23 Historic Treatment of Steel Windows	
49	Please confirm that the government is responsible for detention gun lockers. If not, please provide locations, detail design and quantity required in this project.	Salvage existing detention gun lockers and associated equipment from room 3034 and reinstall per the specifications in new room 3112E.	8/26/2024	Detention Gun Lockers	

1909101 Quad Upgrade ESS - Pre Bid RFI Tracker - 9/10/2024

50	Please confirm that the government will provide a fire watch and security during Fire Suppression & Fire Alarm Outage?	Fire watch personnel is provided by the contractor to cover any outages over the duration of the contract. Security Operations will provide off hours tours of the area the outage covers at an incurred cost to the project.	8/26/2024	Fire Watch	
51	What is the maximum duration allowed for Fire Suppression & Fire Alarm not to be in service?	Measures should be taken to keep outages to as minimal a duration as possible. The contractor should present a plan to minimize outages and it is up to OSHEM's discretion to determine if the plan is acceptable.	8/26/2024	Fire Suppression & Fire Alarm Outage	
52	Please confirm that rebar is not required for entry apron. If yes, please provide rebar arrangement detail.	Rebar not required. Per General Concrete notes G001, reinforced concrete design follows ACI 318-14 (Building Code Requirements for Structural Concrete). For the referenced exterior slab (entry apron), 6x6 W5.5xW5.5 may be used as a minimum reinforcement. Submit location of proposed construction joints to COTR for approval (033000-3.3.B	9/5/2024	G7/C-232ELP1	
53	Please provide the required soil and subbase profile under entry apron.	Reference C-232ELP1	8/26/2024	G7/C-232ELP1	
54	Please provide the product data for Copier (E-3).	Existing copier at OPS office suite will be reused for new office suite. Shredder is NIC.	9/9/2024	A-406EPP1	
55	Specification says Refrigerator/Freezer E-2 shall be a two-door refrigerator with freezer on top and complying with AHAM HRF-1. Product data says 19 Cu. Ft. Single Door Refrigerator (Product Data: FPRU19F8WF). Please provide the correct product data.	Single door refrigerator is the correct type.	8/26/2024	A-406EPP1 / Product Data Page 270 / Specifications	
56	Please provide hardware sets for sets for openings 1011.2, 3112D, 3112E, 3112F.1 & 3112G.	1011.2 = set 510; exclude sound seals and automatic door bottom 3112D = set 510 3112R.1 = set 815 3112G = set 510 3112E = revised set 814, see attached	9/5/2024	Spec 087100	
57	Please provide specifications for Ballistic opening 3112E.	See attached updated specification.	9/5/2024	Ballistic Door 3112E	Yes, 083455 update
58	Comparing the old and new layout, please confirm that the two gypsum board bulkheads are to be demolished.	Confirmed.	8/26/2024	AD405CPP1 (Design Drawing Page 25) & A-405CPP1 (Design Drawing Page 34)	
59	Comparing the old and new layout, please confirm that the ceiling in clouded portion of the drawing is to be demolished.	Confirmed.	8/26/2024	AD402CPP1 Design Drawing Page 22 & A-402CPP1	
60	How many total devices will be monitored?	Please refer to the floorplans where the devices for this effort are shown	9/9/2024	FloorPlans	
61	Would you prefer a yearly or multiyear license?	Please provide a yearly cost with multiyear options	9/9/2024	Security	
62	Do you have an existing server, or do you want this supplied - turnkey?	Please provide turn-key as per specification 280513.10	9/9/2024	Specification 280513.10	
63	Is 'ongoing support' implying that we manage the app and node only? Or, to manage the XX devices being monitored as well?	Ongoing support refers to total system report. Please provide cost breakdown for the above two mentioned options.	9/9/2024	Security	

1909101 Quad Upgrade ESS - Pre Bid RFI Tracker - 9/10/2024

64	Please clarify what type of lock goes on each Access Control Door (Strike or Mortise lock). The drawings have a door schedule but don't have the key to reference back to.	Please refer to Division 8 for locking hardware. TY501DTP1 details call for electrified lockset with Integrated Rex	9/9/2024	Division 8 - TY501DTP	
----	--	---	----------	-----------------------	--