
2003106 - NMAH Renovate Gallery for GunboatPre-Bid RFIs				
#	Reference	RFI	Response	
1		1. Notes 3 and 4 on ED-101 state to determine contents of raceways and trace raceways to their ends, and then remove cables, conductors, and raceways. Bidders are unable to determine quantity or type of cables within the raceways, or the length of the raceway at the time of the bid. Please provide an allowance quantity or dollar value to include.	Keep requirement in notes 3 & 4 to trace raceways to their ends, but at this time, do not assume removal of cables, conducters and raceways. Where possible, cabling & conduit will remain in place and walls furred to accommodate.	
2		2.Note 1 on ET-101 is assumed to relate to notes 3 & 4 on ED-101. Bidders are unable to determine the size of the junction boxes needed, or the length of cable to be installed. Please provide an allowance quantity or dollar value to include.	Disregard note 1 to provide new junction boxes. As indicated in RFI 1 above, where possible, cabling & conduit will remain in place and walls furred to accommodate.	
3		3. Drawing EP 401 EL detail H6 shows a 1" conduit going back to room 3000C5. Do all 3 doors with security get a 1" homerun to room 3000C5 or do all the doors tie back to the 12x12 junction boxes installed with the (2) 2" conduits?	For security related work, 1" conduits route to 12 x 12 junctionbox then back to 2" backbone conduits then to the security closetM2H	
4		4. Drawing TY501 DT Detail 3,5 and 6 show a 1" conduit going back to the security closet. Does each camera need a 1" conduit to the security closet or do they tie into the 12x12 junction boxes installed with the (2) 2" conduits?	Conduits from each camera may tie into 12 x 12 junction box and route the remaining run in the 2" conduit to the closetM2H	
5		5.Please confirm Panel LC3BB will be removed by others.	Panel LC3BB is abandoned. Contractor has no work in Panel LC3BB. In upstream Panel LB3BB, mark three-pole circuit breaker #13 and one-pole circuit breaker #25 "spare"JPA	
6		As per Room Finish Schedule in A-601SH Room 3204 Conservation Space indicates APC (Acoustical Panel Ceiling & Grid).	There should be no new APC in the project. Disregard all requirements for new APC.	
		DIVISION 9 does not include a section for it, and the drawings do not		
7		clarify the comments in the provided elevations.	See response to RFI 6	
8		Please clarify the action to be taken on items on drawing TY-601. There are dash lines all around the security items, is it the SI intention to have the devices replaced?	Dashed lines indicate location of the various security devices and hardware. Data Gathering Panel is existing to remain. All devices in OPS Equipment room are ETR except for Netwrok Switch, PoE+ Enternet Over Fiber Unit, 4 Channel. All devices noted in Gunboat conservation space (3204) and on plans are assumed to be newM2H	
9		What is the current ePACs system that contractors need to integrate to complete the electronic security for the Conservaton Space?	ePACs is an unknown term. PACS (Physical Access Control System) is SoftwareHouse CCURE. This is noted in the 280500.10 - Common Work Results for Electronic Security. Please also note that security vendors must be certified per Section 28 0500.10 Common Work Results for Electronic Security. Please ensure secruity vendors have all 7 Sections (280500.10-Common Work Results for Electronic Security, 280531.10- Communications Equipment for Electornic Security, 280800.10 - Commissioning for Electronic Security, 281000 - Access Control, 281515 Elec5tronic Locking Devices and Accessories, 282000-Video, and 283100 - Intrusion Detection)-M2H	

10	What proprietary system are the existing cameras on? To ensure integration and compatibility	American Dynamics Victor System. This is noted in Section 282000 - Video. Please ensure secruity vendors have all 7 Sections (280500.10-Common Work Results for Electronic Security, 280531.10- Communications Equipment for Electornic Security, 280800.10 - Commissioning for Electronic Security, 281000 - Access Control, 281515 Elec5tronic Locking Devices and Accessories, 282000-Video, and 283100 - Intrusion Detection) - M2H
11	What is the current fire alarm system? Please provide us with the vendor maintenance contact information.	Response from OFMR - Fire shop: Current FA system is Siemens Desigo Fire Safety Modular (XLS). Vendor maintenance contact is SI/OFMR/LSG. Programming contractor for XLS - Siemens Beltsville office. Any changes to program will require them.
12	What is the current BAS system?	Siemens
13	There is mention of asbestos abatement in the statement of work, please provide us with the Conservaton Space asbestos report.	Refer to Addendum #1 to be issued NLT 10/29/24. See also attached records from SI that all other ACM in the space was abated under previous projects.
14	A101 and A601 only indicate a Window Type W1. A202 indicates an additional Window type W2. Please confirm if both windows receive the blackout shade and housing as shown on A502.	Confirmed both windows receive the blackout shade and housing as shown on A502 arch
15	Please confirm if the temporary wall is required to be painted.	Yes, temporary wall should be painted.
16	General note 1 states that any items left in the exhibit are to be removed by the GC. Please clarify what items other than what is shown on AD101 to be removed might be left by SI for removal by the GC.	There are two "boxes" at the lower mezzanine that serve as places were kids can step up and see over the railing. They are incorrectly indicated as Note 201 "Exhibitry removed by Smithsonian" – Please include in GC demo price
17	Please provide dimensions for the new sections of type 4A wall at the ETR Mezzanine 3M205B shown on A101.	All dimensions should be V.I.F. for bidding purposes assume 33LF of type 4A wall at ETR mezzanine 3M205B - arch
18	Please confirm all lumber used for the gunboat protection is to be fire treated.	Yes, all lumber for Gunboat protection must be FRT.
19	Where are the salvaged items being delivered to?	There should only be 2 types of salvaged items. 1) AV monitors. These will be removed by SI prior to the GC starting work. 2) Glass and Wood cases on upper mezzanine. SI requests separate pricing a) to demo the cases b) to remove and relocate to another floor of the building. If needed, an Addendum can be issued requesting these items as a priced option. Updated response 10/25/25. Do not issue a separate price for demo of cabinets. Assume they will be relocated to the 4th or 5th floor via the freight elevator across the hall from the gallery and ~200 LF from elevator.

Please confirm this is required on this project. a.If so, please clarify that the requirement is for an Industrial Hygienist to perform since they do not do this type of work. b.If so, please confirm 3rd party monitoring & testing agency is required and if it is to be a first-tier subcontractor.	Yes, noise and vibration montoring is required per this specification section, but plan may be provided by a par other than an Industrial Hygienist. Vibration monitoring should be provided by a 3rd party monitoring and testin service but is not required to be first-tier subcontractor. Provide breakout pricing for the third party monitoring.
Please confirm if a Service Agreement is required & if so, please provide specifics for	Fire Alarm service agreement not required as part of this
the agreement.	project.
Please confirm location of staging area?	Staging area will likely be the "shop" side of the current gallery. Boat protection will need to be in place before to staging area can be utilized. Upper and lower mezzanine can be used for temporary storage until full boat protection is in place.
Please confirm if contractors may use toilets in NMAH.	Yes, See requirements of Div. 10000 Section 36
Please confirm that the project superintendent may act as QCM and SSHO at the	
	Yes. Superintendent may serve in these roles
Please confirm that all artifacts will be removed by Smithsonian in advance of work.	Yes—There are some larger pieces of the boat which wi be positioned under the boat (by SI) and will be part of what is protected in place
1.The railing had not been removed the day the site walk took place. Who is responsible for removing the railing? Is it the winning bidder or the Smithsonian?2.Does the winning bidder only responsible for demolishing the rail support as mentioned in sheet note 0202?	GC shall demolish the railing. SI will remove textile objection graphic panels prior to demo
Please provide Wall Type 2 detail.	Type 2 is the ETR 2hr rated wall, which receives a new band patch/paint as required by the finish schedule. (see right)
Please clarify if the whole wall will be demolished?	The wall between the gunboat gallery and the Presiden gallery is a rated wall and must remain intact. Demolish items attached to rated wall, including metal shelf suppostats and furring.
1.Please confirm that the stairs and mezzanine level are made of wood (wood deck). 2.Please provide photos of the space below the lower mezzanine level showing the fire suppression pipes.	Yes. Stairs and mezaznine level are wood construction a contains sprinkler piping below. See spec section 02200 Figure 10SI
Please clarify if the lifts will be demo and disposed or demo and salvaged?	Lifts will be demolished and disposed ofSI
	SI requests separate pricing a) to demo the cases b) to- remove and relocate to another floor of the building. If
	a. If so, please clarify that the requirement is for an Industrial Hygienist to perform since they do not do this type of work. b. If so, please confirm 3rd party monitoring & testing agency is required and if it is to be a first-tier subcontractor. Please confirm if a Service Agreement is required & if so, please provide specifics for the agreement. Please confirm location of staging area? Please confirm if contractors may use toilets in NMAH. Please confirm that the project superintendent may act as QCM and SSHO at the same time (Triple Hat)? Please confirm that all artifacts will be removed by Smithsonian in advance of work. 1. The railing had not been removed the day the site walk took place. Who is responsible for removing the railing? Is it the winning bidder or the Smithsonian? 2. Does the winning bidder only responsible for demolishing the rail support as mentioned in sheet note 0202? Please provide Wall Type 2 detail. Please confirm that the stairs and mezzanine level are made of wood (wood deck). 2. Please provide photos of the space below the lower mezzanine level showing the fire suppression pipes.



2 EXISTING 2-HOUR RATED FIRE COMPARTMENT WALL

		Т	Т
	Drawing sheet M-101-FP - Hazardous Materials Warning "Hazardous building materials (HAZMATS) are likely present and are anticipated to be impacted during this project including asbestos containing materials (ACM). There is no safe level of exposure to HAZMATS. Notify the government before disturbing any suspect materials that have not already been identified and await further direction from government ACMS shall be assumed in ductwork mastic."	1. Please confirm that the contractor needs to submit a HAZMAT remediation price for ductwork mastic only. 2. Please confirm that there are no other areas with HAZMAT aside from the ductwork mastic. 3. Is there available HAZMAT report?	Refer to Addendum #1 to be issued NLT 10/29/24. See also attached records from SI that all other ACM in the space was abated under previous projects.
	Drawing AD-101-FP sheet note 0218 "Demo concrete stairway and die wall. Do not remove or damage ETR west wall of 3204C below mezzanine"	Please provide an as-built drawing/or photo below of the concrete stair to see the structure of the stair.	Project number was 0103101- sheets attached arch
	Drawing AD-101-FP sheet note 0229 "Coordinate temporary removal and protection of existing video monitor with SI A/V team."	Please identify where to store or bring the video monitor. Please confirm that the westside wall of the conservation space will receive new	AV monitor will be removed by NMAH staff prior to the start of construciton. No work needed by GC.
35	Conservation Space (3204) westside wall – Room Finish Schedule	plaster and paint.	Confirmed
	Conservation Space (3204) base – Room Finish Schedule	Please confirm that the 4 walls of the conservation space will receive new 4" high vinyl base.	Confirmed
37	Conservation Space (3204) eastside wall – Room Finish Schedule	1.Please confirm that the eastside wall of the conservation space will receive new gypsum wallboard and paint. 2.As per East elevation at drawing 2 sheet A-201-EL, it will only receive patching and paint. Please clarify.	2 From spec section 022000 Figure 10, we know there is metal mesh on the conservation space face. Assume new GB on the face of this wall to encapsulate metal mesh at under under demo'd mezzanine. The remainder of the wall can be patched and painted.
38	Conservation Space (3204) southside wall – Room Finish Schedule	1.Please confirm that the southside wall of the conservation space will receive new gypsum wallboard and paint. 2.As per South elevation at drawing 1 sheet A-201-EL, ETR mezzanine wall will only receive patching and paint. Please clarify. 3.Please confirm if the southside of the conservation space where the handrail is demoed will receive new work. If yes, will it receive new GWB and paint as per the room schedule?	1. southside wall of conservation space is new 1 hr rated partition wall, therefore it will received new GWB and paint. 2 & 3. We know there is a full GWB wall separating the collections storage space (south and west) from the area under the mezzanine, but the condition of this wall is unknown. A new layer of GWB or patching is acceptable, however note that Specifications call for Level 5 finish. Instead, provide Level 4 finish inside the conservation space (3204).
39	Conservation Space (3204) ceiling – Room Finish Schedule	1.Please confirm that APC will be installed in Conservation Space. 2.If yes, please provide a ceiling plan that reflects the APC layout. 3.Please provide APC & grid specifications	There should be no new APC in the project. Disregard all requirements for new APC.
40	Landmark 3E (3020) Base – Room Finish Schedule	Please confirm that this is not part of the contract. Please confirm that the eastside wall of the ETR Mezzanine will receive new gypsum	3020 has scope required by the room finish schedule A 601 SH. See response to RFI 69. The east side of the ETR Mezzanine is the next to the 3205.
41	ETR Mezzanine (3M205B) Eastside wall – Room Finish Schedule	wallboard and paint.	No work is anticipated here.
	ETR Mezzanine (3M205B) Southside wall – Room Finish Schedule	Please confirm that the Southside wall of the ETR Mezzanine will receive new gypsum wallboard and paint.	At this wall we expect that full replacement will be required because of the extent of demolition. To be confirmed in field. Note, Specifications call for Level 5 finish. Instead, provide Level 4 finish inside the conservation space (3204).

43	ETR Mezzanine (3M205B) Westside wall – Room Finish Schedule ETR Mezzanine (3M205B) & Conservation Space (3204) – Room Finish	1. Please confirm that the Westside wall of the ETR Mezzanine will receive plaster and paint. 2. Please point out in the plan of the wall that needs to receive plaster. As per room schedule, ETR mezzanine is exposed ceiling and conservation space will	See elevations. Patching at existing portion of wall is acceptable, but where the stairs were removed, we expect that full replacement will be required because of the extent of demolition. To be confirmed in field. Note, Specifications call for Level 5 finish. Instead, provide Level 4 finish inside the conservation space (3204). There should be no new APC in the project. Disregard all
44	Schedule	have APC. Please provide APC termination details.	requirements for new APC.
	Specification Section 054000 – Cold-Formed Metal Framing Item 1.3.C.1	Please confirm if the delegated design for cold-formed steel framing is required.	spec 054000 requires delegated design- arch
	Hazmat Report	Is there a hazmat report available for the gallery?	Refer to Addendum #1 to be issued NLT 10/29/24. See also attached records from SI that all other ACM in the space was abated under previous projects.
	Liquidated Damages	Are there liquidated damages in this project? If yes, how much?	No liquidated damages
	Toilet	Will the workers allowed to use the public toilet?	Yes, See requirements of Div. 10000 Section 36 -SI
	Parking	Will there be designated parking for the project superintendent?	No designated parking will be provided -SI
43	Specification section 010000 item 34.1 "The contractor shall establish a	With there be designated parking for the project superintendent:	No. A temporary office is not required. Contractor can use
F0	1 '	Please confirm if a temporary office is required during the construction.	
	temporary office at the project site. "		gallery space once boat is protectedSI
51	As-built CAD record drawing	Does the contractor required to provide a CAD as built?	No. CAD as-builts are not requiredSI
52	Window Schedule	Please provide a window schedule	The Project has two windows W1 and W2 Shown on A 202 EL, A 502 DT and spec 08 8817
53	Roller Window Shades	1.Please provide shade dimensions 2.Please confirm that W1 & W2 windows will receive manual blackout shade & housing.	1- Shades are full width of each window 2- Confirmed W1 and W2 both recive manual blackout shades and housings -arch
54	Room ID Sign	Please confirm that the contractor will only provide signs for the following: 1.(2) ID signs for Conservation Space 2.(1) ID sign for Mechanical Room	Confirmed -arch
55	replace 6th pane from planter with louver and Window detail."	Please confirm if this is part of the contract. If yes, please provide clear instructions. (provide detail drawings and specs)	This is not part of the project. Disregard referenct for louver and exterior window workSI
56	Sign-in sheet	Please provide a copy of the sign-in sheet.	See attached.
57	Staging & Laydown Area	Will the government provide a space for staging and laydown area?	Staging/layodown area will likely be the "shop" side of the current gallery. Boat protection will need to be in place before this staging area can be utilized. Upper and lower mezzanines can be used for temporary storage until full boat protection is in place.
	Storage	Will the government provide temporary storage for the winning bidder?	Temporary storage area/staging area will likely be the "shop" side of the current gallery. Boat protection will need to be in place before this staging area can be utilized. Upper and lower mezzanines can be used for temporary storage until full boat protection is in place
59	Reference: Specification Section 101423.16 item 1.2.A "Section includes room-identification signs that are directly attached to the building. Signs must match existing signs in building."	Please provide a sample of the existing signs in the building. (Photo)	See photos to the right





		Please confirm that the delegated design for cold-formed steel framing and for the		SPENNIE LOSS ID
60	Reference: Delegated Design	manufactured metal ladder.	Confirmed	
	Neichenee. Delegated Design	1.Is there any third-party testing & Inspection involved in this contract?	Committee	
61	Third Party Testing & Inspection	2. If yes, is the winning contractor be responsible for it?	Provide per documents.	
- 01	Third Furty resting a hispection	1.Does field test joint-sealant adhesion require in this contract?	Trovide per documents.	
62	 Field test joint-sealant adhesion	2. Does it require a third-party testing company?	Provide per documents.	
	Specification Section 087100 item 3.4.A.1 – Independent Architectural	2.Does rerequire a tima party testing company.		
	Hardware Consultant state "Engage a qualified independent Architectural			
	Hardware Consultant to perform inspections and to prepare inspection	Please confirm that this is not applicable to this project.		
63	reports."	Trease committed this is not applicable to this project.	Provide per documents.	
- 03			Trovide per documents.	
	Drawing AD-101-FP Legend T1 "Provide temporary construction partition			
	until new perimeter walls, windows, and doors are erected. Build	1.Can we use the 1-hour temporary construction partition to build the rated partition	Provide a temporary partition per the project documents.	
	<u> </u>	enclosing new conservation space (permanent wall)?		
	construction barriers from floor to ceiling. Provide pair doors, 915mm x		Any early removal of the temporary partition would need	
	2134mm (3'-0") x 7'-0"), frame, and hasp with padlock. Coordinate	2. If it is allowed to use the temporary partition for the permanent wall, is it possible to	to be coordinated and approved in advance by COTR and	
	location w/ COTR" – 1 hour fire rated wall.	demolish the temporary construction partition sooner to build the rated partition	should not be assumed. SI is open to how the wall is built,	
	Drawing A-101-FP Note 0502 "New wall must align with edge of ETR metal	enclosing the new conservation space (permanent wall)?	as long as the 1 hr. wall is in the same plane as the existing,	
	ceiling without damage to ceiling (permanent wall/wall enclosure)" – 1		and the boat and adjacent corridor are protected from	
64	hour fire rated wall.		dust and noise.	
	Specification Section 01 91 13 – Commissioning Item 1.1.A. "The	42.Reference:		
	Smithsonian will procure the services of independent Commissioning	Question: Please confirm that a third-party commissioning consultant is required and	Third party Commissioning is not required for the scope of	
65	Consultant"	will be hired by the Smithsonian.	this project.	
	Initial RFI submission October 21, 2024 and RFI Responses issued October			
66	24, 2024, that display an empty yellow box in the Response column.		Empty response boxes are complete.	
	RFI #19 answer "There should only be 2 types of salvaged items. 1) AV	Please provide an addendum for these items as a priced option.		
	monitors. These will be removed by SI prior to the GC starting work. 2)			
	Glass and Wood cases on upper mezzanine. SI requests separate pricing			
	a) to demo the cases b) to remove and relocate to another floor of the		See revised reponse to RFI 19 and 31 removing the	
	building. If needed, an Addendum can be issued requesting these items as		requirement for a priced option and giving estimates of	
67	a priced option."		travel distance for salvaged cases.	
		What floor and total distance do we need to relocate the items?		
	RFI #31 answer "SI requests separate pricing a) to demo the cases b) to		See revised reponse to RFI 19 and 31 removing the	
	remove and relocate to another floor of the building. If needed, an		requirement for a priced option and giving estimates of	
68	Addendum can be issued requesting these items as a priced option."		travel distance for salvaged cases.	
	DEL #40 - manuar (/ 2020)		See Sheet A202EL and A601SH. Rooms 3020 and 3000C6	
	RFI #40 answer " 3020 has scope required by the room finish schedule A		are both open corridor spaces and flow into each other.	
	601 SH – arch"	Please point out the location in the drawing where we need to install the new vinyl base	Paint and vinyl base is only required at new 1 hr rated wall	
69		and the new GWB & paint.	along public corridor/landmark space to match adjacent	